

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20296-00-01
Spot: NWNESW Sec/Twnshp/Rge: 12-16S-43W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: GARRISON A Well #: 5
County: GREELEY Total Vertical Depth: 5265 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4980		WITH 2 SX CMT
SURF	8.625	464		WITH 320 SX CMT 171.11
PC		1754		WITH 225 SX CMT
PROD	4.5	5265	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2009 3:00 PM
Plug Co. License No.: 34249 Plug Co. Name: SANJEL (USA) INC.
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (618) 943-2227

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2009 7:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 4980' WITH 2 SX CMT. 2ND PLUG PERFORATE 4 1/2" @ 1000'. 3RD PLUG RIHWT TO 2800'. PUMP 478 SX CMT. CIRCULATED 4 1/2" WITH 177 SX CMT. CIRCULATE 4 1/2" X 8 5/8" ANNULUS FROM 1000'-0' WITH 301 SX CMT. 4TH PLUG WAIT ON CMT 1 HOUR. TOPPED CASING OFF WITH 60 SX CMT. WAIT ON CMT 1 HOUR TOPPED ANNULUS WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5120	5144		

INVOICED
DATE: 12.29.09
INV. NO. 2010060637

RECEIVED
NOV 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL SANJEL.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

OCT 28 2009

KCC DODGE CITY

Form CP-2/3