

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20393-00-02
Spot: NESENE Sec/Twnshp/Rge: 1-16S-43W
1650 feet from N Section Line, 330 feet from E Section Line
Lease Name: EDSALL F Well #: 8
County: GREELEY Total Vertical Depth: 5300 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5052		WITH 2 SX CMT
SURF	8.625	384		WITH 200 SX CMT 172.25
PC		2772		WITH 350 SX CMT
PROD	4.5	5300	0	WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2009 9:00 AM
Plug Co. License No.: 34249 Plug Co. Name: SANJEL (USA) INC.
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (618) 943-2227

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: _____ KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD 5248'. 1ST PLUG SET CIBP @ 5050' WITH 2 SX CMT. 2ND PLUG RIHWT TO 2803' & PUMP 80 SX CMT. 3RD PLUG PERFORATE @ 1300'. ESTABLISH RATE. PUMP 80 SX CMT, DROP 10 BALL SEALERS & 80 SX CMT. SHUT IN PRESSURE 800 PSI. 4TH PLUG PUMP DOWN 4 1/2" X 8 5/8" ANNULUS WITH 160 SX CMT. SHUT IN PRESSURE 50 PSI.

Perfs:

Top	Bot	Thru	Comments
5102	5118		

INVOICED
DATE: 12.29-09
INV. NO. 2010060637

RECEIVED
NOV 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SANJEL.

Plugged through: CSG

District: 01

RECEIVED

OCT 28 2009

KCC DODGE CITY

Signed



(TECHNICIAN)

Form CP-20

