

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20779-00-00
Spot: NWSESW Sec/Twnshp/Rge: 6-19S-4E
957 feet from S Section Line, 3562 feet from E Section Line
Lease Name: JIRAK A Well #: 1
County: MARION Total Vertical Depth: 2400 feet

Operator License No.: 30483
Op Name: KREMEIER, LES DBA KREMEIER PROD
Address: 3183 US HWY 56
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		
PROD	4.5	2398	1131	

78.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/01/2009 8:00 AM
Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES DBA KREMEIER PROD. AND OPER. CO.
Proposal Rcvd. from: KREMEIER PRODUCTION Company: _____ Phone: (785) 258-2321

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: SHANE JONES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2009 3:45 PM KCC Agent: SHANE JONES

Actual Plugging Report:

10/28/2009 WELL TO HAVE BEEN PLUGGED BY TODAY AS PER COMMISSION ORDER. NO PLUGGING DONE BY THIS DAY. I NOTIFIED JEFF KLOCK, WHO WILL CONTACT LEGAL. 11/10/2009 KREMIER MOVED IN TO START PLUGGING TODAY. KREMEIER RAN TUBING TO 2325' AND CONSOLIDATED PUMPED 35 SXS W/3% CALCIUM FOR A BOTTOM PLUG. KREMEIER PULLED TUBING AND LOG-TECH SHOT OFF CASING @ 1316'. CASING DID NOT PULL FREE. LOG-TECH CAME UP TO 1131' AND SHOT OFF CASING. KREMEIER PULLED 4.5" CASING. KREMEIER THEN RAN TUBING BACK INTO 278' AND CIRCULATED CEMENT TO SURFACE. USED 35 SXS 60/40 POS W/3% CALCIUM + 126 SXS 60/40 POS W/4% GEL FOR A TOTAL OF 161 SXS CEMENT. TK #2316. 11/12/2009 CHECKED TOP PLUG FELL 30'. KREMEIER DRY SACKED IT TO SURFACE W 5 SXS COMMON CEMENT.

Perfs:

Top	Bot	Thru	Comments
2246	2262		
2346	2362		

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 23 2009

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE: 12.29.09
INV NO. 2010040640

Remarks: GPS LAT: 38.42339, LONG: -097.03471

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

PKT

15