

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Te-Pe Oil & Gas
Address: P.O. Box 522, Canton, KS 67428
Phone: (620) 628-4428 Operator License #: 5920

API Number: 15-185-12866-00-00
Lease Name: Aiken
Well Number: #2

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): _____ - NW - SE - NW
1,650' Feet from North / South Section Line
1,650' Feet from East / West Section Line

The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)

Sec. 20 Twp. 22 S. R. 11 East West
County: Stafford

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Date Well Completed: 08/15/53
Plugging Commenced: 10/19/09
Plugging Completed: 10/20/09

Producing Formation(s): List All (If needed attach another sheet)

Simson Depth to Top: 3560 Bottom: 3565 T.D. _____
Arbuckle Depth to Top: 3569 Bottom: 3640 T.D. 3640
_____ Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Simson</u>	<u>Oil & water</u>					
<u>Arbuckle</u>	<u>Oil & water</u>					
				<u>8 5/8"</u>	<u>192'</u>	<u>0</u>
				<u>5 1/2"</u>	<u>3,640'</u>	<u>1,630'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Had 8" stretch; Sand was at 3,340'. Bailed 5 sacks cement with bailer. Cut surface off 4' below ground. Ripped casing at 2,010', 1,840' and 1,630'.
Pipe came free at 1,630'. Pulled casing up to 600'; Pumped 10 gel and 50 sacks 100# hulls. Pulled to 220'; Pumped 50 sacks 100# hulls. Pulled to 40'; Pumped 20 sacks to surface.

RECEIVED

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

NOV 05 2009

Name of Party Responsible for Plugging Fees: Te-Pe Oil & Gas

KCC WICHITA

State of Kansas County, McPherson, ss.

Jerry Bandy (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: (that) have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct. I help me God.

(Signature) Jerry Bandy
(Address) P.O. Box 522, Canton, KS 67428

SUBSCRIBED and SWORN TO before me this 2nd day of November, 2009
Cynthia G. Bereke My Commission Expires: May 15, 2010
Notary Public

