

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3273
Name: Herman Loeb
Address 1: PO Box 838
Address 2: _____
City: Lawrenceville State: ILL Zip: 62439 + _____
Contact Person: Ed Loeb
Phone: (618) 943-2227
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 1460 Bottom: 1500 T.D. CIBP 1625
_____ Depth to Top: 5131 Bottom: 5146 T.D. CIBP 5100
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 071-20294 -00-00
Spot Description: _____
NE-SW-NE Sec. 11 Twp. 16 S. R. 43 East West
1,650 3041 Feet from North South Line of Section
1,650 1675 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Greeley
Lease Name: Edsall Well #: E-5
Date Well Completed: _____
The plugging proposal was approved on: 10/14/09 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 10/19/09
Plugging Completed: 10/19/09 3:30PM

KCC PCT
PCT
CP213

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|-------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | Surface | 8 5/8 | 520 | none |
| | | Production | 4 1/2 | 5100 | none |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP c/o 1625, fill 4 1/2" casing w/cement from 1500' to 0' using 40 ball sealers, 150# walnut hulls & 116 sx cement. Fill 4 1/2 X 8 5/8 annulus to 0' w/12 sx. Pressure to 1500#. Plugging complete

RECEIVED
NOV 05 2009
KCC WICHITA

Plugging Contractor License #: 34249 Name: Sanjel Inc
Address 1: 200505 2nd St SW Address 2: _____
City: Calgary, Alberta State: Canada Zip: T2P1N8 + _____
Phone: (403) 269-1420
Name of Party Responsible for Plugging Fees: Herman Loeb
State of Kansas County, _____, ss.
Shane Peiten Employee of Operator or Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

PCT