

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 3273  
Name: Herman Loeb LC  
Address 1: PO Box 838  
Address 2: \_\_\_\_\_  
City: Lawrenceville State: ILL Zip: 62439 + \_\_\_\_\_  
Contact Person: Ed Loeb  
Phone: (618) 943-2227  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 5102 Bottom: 5118 T.D. 5300  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 071-20000-00-02 <sup>80393</sup>  
Spot Description: \_\_\_\_\_  
NE SE NE Sec. 1 Twp. 16 S. R. 43  East  West  
1650 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Greeley  
Lease Name: Edsall Well #: F-8  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 10/14/09 (Date)  
by: Ken Jehlik (KCC District Agent's Name)  
Plugging Commenced: 10/19/09  
Plugging Completed: 10/19/09 12:30PM

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
marrow		Surface	8 5/8	384	none
		Production	4 1/2	5300	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP w/ 2 sx cement c/o 5050. 80 sx plug c/o 2803' thru tubing TOOH w/ tubing. Perf 3 holes c/o 1300' inj. rate 3 bpm c/o 500#. Pump 80 sx, 10 ball sealers, then 80 sx. Pressure increase 350 to 800#. Casing stayed full. No blow or circulation up 4 1/2 X 8 5/8 annulus. Pump 160 sx down 4 1/2 X 8 5/8 annulus to 250 psi. Holding 50 psi. Plugging complete

RECEIVED  
NOV 05 2009

Plugging Contractor License #: 34249 Name: Sanjel Inc  
Address 1: 200505 2nd St SW Address 2: \_\_\_\_\_  
City: Calgary, Alberta State: Canada Zip: T2P1N8 + \_\_\_\_\_  
Phone: (403) 269-1420  
Name of Party Responsible for Plugging Fees: Herman Loeb  
State of Kansas County, \_\_\_\_\_, ss.  
Shane Pelton  Employee of Operator or  Operator on above-described well,  
(Print Name)

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

*[Handwritten Signature]*