

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5663
Name: Hess Oil Company
Address 1: P. O. Box 1009
Address 2: _____
City: McPherson State: KS Zip: 67460 + 1009
Contact Person: Bryan Hess
Phone: (620) 241-4640
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Viola Depth to Top: 3401 Bottom: 3402 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 113-20,428-00-00
Description: Approx
N2-S2 NW NE Sec. 1 Twp. 20 S. R. 2 East West
820 4443 Feet from North South Line of Section
1980 1951 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: McPherson
Lease Name: Minnie Johnson Well #: 2
Date Well Completed: 4-28-1977
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 10-6-2009
Plugging Completed: 10-12-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	163'	none
		Production	5-1/2"	3424'	1603'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged bottom with sand to 2880' and 5 sacks cement. Cut casing loose @ 1603', pulled to 450', pumped 35 sx 60/40 pozmix, 4% gel, pulled casing to 254', and circulated 80 sx to surface. Laid down the rest of the casing.

Plugging Contractor License #: 31528 Name: Mike's Testing & Salvage, Inc.
Address 1: P. O. Box 467 Address 2: _____
City: Chase State: KS Zip: 67524 + 0467
Phone: (620) 938-2943

Name of Party Responsible for Plugging Fees: Hess Oil Company
State of Kansas County, McPherson, ss.
Bryan Hess, President Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Bryan Hess

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC PRT PM
CP 213

Kelso, Mike Oil Inc

RECEIVED
NOV 09 2009

KCC WICHITA

KCC
PRT
PM
OPS

PKT

