

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34110  
Name: Teton North America LLC  
Address 1: 600 17th St., Suite 1600  
Address 2: \_\_\_\_\_  
City: Denver State: CO Zip: 80202 + \_\_\_\_\_  
Contact Person: Steve Godfrey  
Phone: ( 303 ) 565-460-\_\_\_\_\_  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-25261-00-00  
Spot Description: \_\_\_\_\_  
NW NW 1/4 Sec. 18 Twp. 17 S. R. 13  East  West  
702 Feet from  North /  South Line of Section  
676 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Woydziak Well #: 11-18  
Date Well Completed: n/a  
The plugging proposal was approved on: 10/12/08 (Date)  
by: Bruce Rodie (KCC District Agent's Name)  
Plugging Commenced: 10/14/08  
Plugging Completed: 10/14/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC 3219-3422	none	Surface	8-5/8	939	No
Arb 3436-3525	none				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Data:  
Received plugging orders from Bruce Rodie on 10/12/08 at 8:00 pm. Heavy mud in hole and between all plugs. Bottom plug at 3415' w/25sks, 2nd plug at 1240' w/100 sks, top plug at 40' w/10 sks cemented to surface. plugged rathole w/30 sks, no mousehole Total of 165 sks of 60/40 Poz with 4% Gel & 1/4# FS/sk. complete at 5:15 pm on 10/13/08. Quality Cementing ticket # 2114. Sterling reported plugging to KCC on 10/14/08.

Plugging Contractor License #: 5142 Name: Sterling Drilling Co.  
Address 1: Box 1006 Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + 1006  
Phone: ( 620 ) 672-9508  
Name of Party Responsible for Plugging Fees: Teton North America, LLC  
State of Colorado County, Denver, ss.  
Steve Godfrey  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_ 11/5/09 \_\_\_\_\_

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
NOV 10 2009  
KCC WICHITA