

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4787  
Name: TDI, Inc.  
Address 1: 1310 Bison Road  
Address 2: \_\_\_\_\_  
City: Hays State: KS Zip: 67601 + 9696  
Contact Person: Tom Denning  
Phone: (785) 628-2593  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 051-25901-00-00  
Spot Description: \_\_\_\_\_  
E2 E2 NW NW Sec. 28 Twp. 14 S. R. 16  East  West  
660 Feet from  North /  South Line of Section  
1,075 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Rajewski Well #: 1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 10-30-2009 (Date)  
by: Richard William (KCC District Agent's Name)  
Plugging Commenced: 11-01-2009  
Plugging Completed: 11-01-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8"	219	none


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug: 3400' w/25 sacks cement through drillpipe  
2nd plug: 1040' w/25 sacks cement through drillpipe  
3rd plug: 420' w/80 sacks cement through drillpipe  
4th plug: 40' w/ 10 sacks cement through drillpipe  
30 sacks cement in rat hole and 15 sacks cement in mouse hole

RECEIVED  
NOV 16 2009  
KCC WICHITA

Plugging Contractor License #: 5929 Name: Duke Drilling Co., Inc.  
Address 1: P. O. Box 823 Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: (620) 793-8366  
Name of Party Responsible for Plugging Fees: TDI, Inc.  
State of Kansas County, Ellis, ss.  
Tom Denning  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature:   
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



# ALLIED CEMENTING CO., LLC. 038549

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: R-11111

DATE <u>11-1-09</u>	SEC. <u>2P</u>	TWP. <u>14S</u>	RANGE <u>16W</u>	CALLED OUT	ON LOCATION	JOB START <u>7:00 AM</u>	JOB FINISH <u>4:30 AM</u>
LEASE <u>Rajewski</u>		WELL# <u>1</u>	LOCATION <u>Walker T-20</u>			COUNTY <u>Ellis</u>	STATE <u>Ks</u>
OLD OR NEW (Circle one) <u>NEW</u>			<u>3 1/2 S 1 1/2 W Sinks</u>				

CONTRACTOR <u>Duke Drilling R3 #2</u>	OWNER _____
TYPE OF JOB <u>Rotary Plug</u>	CEMENT
HOLE SIZE <u>7 1/2"</u> T.D. <u>35-25</u>	AMOUNT ORDERED <u>185 @ 4.8 Gal</u>
CASING SIZE _____ DEPTH _____	<u>14 #56</u>
TUBING SIZE _____ DEPTH _____	
DRILL PIPE <u>4 1/2"</u> DEPTH <u>3400</u>	
TOOL _____ DEPTH _____	
PRES. MAX _____ MINIMUM _____	COMMON <u>111</u> @ <u>13.50</u> <u>1,498.50</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX <u>74</u> @ <u>7.55</u> <u>558.70</u>
CEMENT LEFT IN CSG. _____	GEL <u>6</u> @ <u>20.25</u> <u>121.50</u>
PERFS. _____	CHLORIDE @ _____
DISPLACEMENT _____	ASC @ _____

EQUIPMENT	
PUMP TRUCK CEMENTER <u>Shane</u>	
# <u>412</u> HELPER <u>Matt</u>	
BULK TRUCK	
# <u>410</u> DRIVER <u>Wagac</u>	
BULK TRUCK	
# _____ DRIVER _____	

RECEIVED  
NOV 16 2009  
KCC WICHITA

REMARKS:  
3400' 1st Plug with 25 skt  
1040' 2nd Plug with 25 skt  
425' 3rd Plug with 50 skt  
40' 4th Plug with 10 skt  
Rot Hole 30 skt  
Misc Hole 15 skt

HANDLING <u>92</u> @ <u>2.25</u> <u>207.00</u>
MILEAGE <u>110/sk/mile</u> <u>300.00</u>
TOTAL <u>2796.40</u>

CHARGE TO: T O I INC.  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>991.00</u>
EXTRA FOOTAGE @ _____	
MILEAGE <u>15</u> @ <u>7.00</u> <u>105.00</u>	
MANIFOLD @ _____	
_____ @ _____	
_____ @ _____	
TOTAL <u>1096.00</u>	

Mack

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

_____ @ _____	
<u>Dry 166 Plug</u> @ _____	<u>N-C</u>
_____ @ _____	
_____ @ _____	
TOTAL _____	

PRINTED NAME \_\_\_\_\_  
 SIGNATURE Todd Leek

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES [scribble]  
 DISCOUNT [scribble] IF PAID IN 30 DAYS