


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks _____ County. Sec. 30 Twp. 10S Rge. 20W (E) _____ (W) _____
Location as "NE/CNW/SE/SW" or footage from lines. SE 1/4 SE 1/4 NW 1/4
Lease ~~Owner~~ Operator: Birmingham-Bartlett Drilling Co.
Lease Name Raymond "A" Well No. 1
Office Address 300 Kaufman Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 2 19 52
Application for plugging filed (Verbal approval rec'd) 11-4 19 52
(on 11-2-52) " " 19
Application for plugging approved _____
Plugging commenced November 2 19 52
Plugging completed November 2 19 52
Reason for abandonment of well or producing formation No shows



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Congl. 3637 (No Arbuckle) Depth to top 3637' Bottom 3710' Total Depth of Well 3710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	168'	8-5/8	162'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with 1/2 sack hulls and 15 sacks cement on bottom plug set at 165'; 1/2 sack hulls and 10 sacks cement on top plug set at 40'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address 300 Kaufman Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.
(Signature) By Richard Hindery Partner
300 Kaufman Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November 1952.

My commission expires November 29, 1954
Vivian L. Ginger Notary Public.

PLUGGING
FILE SEC 30 T 10 R 20S
BOOK PAGE 56 LINE 42

STATE OF KANSAS
11-5-1952
NOTARY PUBLIC
CONSERVATION DIVISION
Wichita, Kansas

RAYMOND "A" #1 WELL

LOCATION: NE $\frac{1}{4}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$ Sec. 30-10S-20W
Rooks County, Kansas

SPURDEND: 10-21-52

OPERATOR: Birmingham-Bartlett Drilling Co.

COMPLETED: 11-2-52

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8-5/8" casing cemented at 162'
with 125 sacks cement and 2 c.c.

OIL STRING: None Run

LOG

(Figures indicate bottom of formation)

0	to	105	Clay and Shale
		168	Shale & Shells
		1050	Shale & Sand
		1250	Sand
		1590	Shale & Shells
		1620	Anhydrite
		2220	Shale & Shells
		2330	Shale & Lime
		2360	Lime
		2450	Shale & Shells
		2515	Shale
		2695	Shale & Lime
		2815	Shale
		3130	Lime & Shale
		3190	Lime
		3245	Lime & Shale
		3330	Lime
		3385	Lime & Shale
		3470	Lime
		3490	Lime & Shale
		3562	Lime
		3610	Lime & Shale
		3655	Lime
		3683	Lime & Shale
		3710	Shale & Chert
		3710	Rotary Total Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Raymond "A" #1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn before me
this 4th day of November, 1952

Virgil J. Ginger

Notary Public

PLUGGING
WELL SEC. 30 T. 10 R. 20
BOOK PAGE 56 LINE 42

My commission expires

November 29, 1954

STATE COMMISSION
11-5-1952

CONGRESS
MAY 1952