

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-22900-00-00

API NUMBER 15-163-22,900

LEASE NAME Allphin

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 30 TWP. 10 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 12-18-86

Plugging Commenced 12-18-86

Plugging Completed 12-18-86

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 1105 E. 30th, Suite 'A', Hays, KS 67601

PHONE# (913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	218'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3740'-3720' 40 sks cement @ 260'

25 sks cement @ 3720' 10 sks cement @ 40'

25 sks cement @ 1625' 15 sks cement in rathole.

100 sks cement @ 880'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]
Kyle B. Branum

(Address) P. O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 19 86

[Signature]
Glenda R. Tiffin, Notary Public

My Commission Expires: February 6, 1988



STATE CORPORATION COMMISSION

12-23-1986
DEC 23 1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

EMPHASIS OIL OPERATIONS

P. O. Box 506
Russell, KS 67665

DRILLERS LOG

OPERATOR: Black Diamond Oil, Inc.
1105 E. 30th, Suite A
Hays, KS 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Allphin

WELL #1

LOCATION: SE SE NE
Section 30-10S-20W
Rooks County, Kansas

Log Total Depth: 3738'

Rotary Total Depth: 3740'

Commenced: 12/11/86

Casing: 8-5/8" @ 218' w/150 sks cement

Elevation: 2155' K.B.

Completed: 12/18/86

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top soil & Sand	30'	Shale	1588'
Shale	220'	Anhydryte	1631'
Shale & Sand	740'	Shale	2313'
Dakota Sand	850'	Shale & Lime	3321'
Shale	1040'	Lime (R.T.D.)	3740'
Cedar Hills	1260'		

STATE CORPORATION COMMISSION

12-23-1986
DEC 23 1986

STATE OF KANSAS)
) SS
COUNTY OF RUSSELL)

CONSERVATION DIVISION
Wichita, Kansas

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Kyle B. Branum

Kyle B. Branum

Subscribed and sworn to before me this 22nd of December, 1986.
My Commission Expires: July 29, 1989.

PATRICIA L. SCHAWO
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 7/29/89

Patricia L. Schawo

Patricia L. Schawo, Notary Public