

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD 15-163-00411-00-01
K.A.R.-82-3-117

API NUMBER 8-1-50

LEASE NAME Raymond

WELL NUMBER 1

SPOT LOCATION NW NW NW

SEC. 30 TWP. 10RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 8-1-50

Plugging Commenced 5-9-90

Plugging Completed 5-9-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # 913 628 6101 OPERATORS LICENSE NO. 5245

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. 67601

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 3804

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	163	8 5/8		None
	Casing	0	3706	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Clean out to 2200'. Rig up BJ Titan and mix 5 sks. gel and 100sks. common with 100# hulls. Pull 26 its. and mix 250 sks. 65/35 pos. 8% gel, 1/4# colloflake per sk. 400# hulls. No circulation. Pull 5 its. Mix 50 sks. 65/35 pos. 8% gel, 1/4# colloflake per sk. Cement to surface. Pull tbg. Hook to 5 1/2. Mix 20 sks. 65/35 pos. 8% gel, 1/4# colloflake per sk. Hook to 8 5/8. Mix 12 sks. Shut in 350#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723 Hays, Kansas 67601

BJ Titan cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(employee of operator) or


(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks. 67601

SUBSCRIBED AND SWORN TO before me this 12 day of May, 1990

Rosemary Smith
Notary Public



My Commission expires: 5-1-1991

MAY 14 1990
5-14-1990
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 06-83