

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 30 Twp. 109 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE

Lease Owner Trans Era Petroleum, Inc.

Lease Name Schneider "D" Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 4/28/53 19

Application for plugging filed 4/27/53 19

Application for plugging approved 4/27/53 19

Plugging commenced 4/28/53 19

Plugging completed 4/28/53 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3712 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Finished laying down drill pipe. Filled hole with heavy mud to 200', set first plug together with 15 sacks of cement through drill pipe. Top plug was set at 40' with 10 sacks of cement and 1/2 sack of hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis

Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 53

My commission expires 1-30-57

Margie Cooper Notary Public.

PLUGGING
FILE SEC 30 T 10 R 20 W
BOOK PAGE 98 LINE 27

5-2-1953
CONSERVATION DIVISION
WICHITA, KANSAS

Trans Era Petroleum, Inc.
Schneider "B" #1

NW SW SE 30-10-20
Rooks County, Ks.

Total Depth: 3712'
Comm. 4/16/53
Comp. 4/28/53

Casing

8 5/8" Set @ 213'

Cement

135 sacks of Lone Star

Formation	Depth
Surface clay-sand	30
Sand-shale	75
Shale-shells	213
Sand-shale	286
Shale-sand-red bed	1558
Anhydrite	1570
Shale-shells	1760
Shale-sand	1900
Shale-shells	1968
Shale	2180
Lime-shale-shells	2295
Shale-shells	2430
Shale-lime	3362
Lime	3600
Lime-shale	3616
Shale	3652
Conglomerate	3712'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

5-2-1953

Cora B. [Signature]

Subscribed and sworn to before me this 1st day of May, 1953.

Margie Cooper

Notary Public

My commission expires: 1-30-57.

PLUGGING
FILE SEC 30 T 10 R 10
BOOK PAGE 27 LINE 27