


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks County. Sec. 30 Twp. 10 Rge. 20 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Sierra Petroleum Company, Inc.

Lease Name Schneider Well No. B-1

Office Address P. O. Box 232 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_

Plugging commenced 12-20-69 19\_\_

Plugging completed 12-29-69 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3672 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	215	None
				5 1/2	None	607
RECEIVED STATE CORPORATION COMMISSION 1-6-1970 JAN 6 1970 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved unit to location. Rigged up pole. Starting to dig cellar.

Finished rigging up jacks - had 8" tension. Sanded well to 3650' and dumped 5 sacks of cement.

Shot casing at 1000' - 800' and 600'. Pulled 20 joints of 5 1/2" casing.

Allied squeezed well with 15 sacks of mud - 3 sacks of hulls and 100 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.

Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) James W. Rockhold

P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of December, 19 69

My commission expires May 27, 1973

(Signature)  
Notary Public.



B & R Drilling, Inc.  
Schneider "B" #1

NW NW SE 30-10-20  
Ellis County, Kans.

Total Depth: 3672'  
Comm. 8/16/52  
Comp. 8/30/52

Casing

8 5/8" Set @ 215'  
5 1/2" Set @ 3368 1/2'  
6

Cement

135 sacks Ash Grove  
100 sacks Ash Grove

Formation	Depth
Soft lime-shale	190
Shale	560
Shale-shells	720
Shale-sand	900
Shale-shells	1130
Shale-sand	1290
Shale-shells-red bed	1530
Shale-shells	1590
Shale	1815
Shale-shells-red bed	2120
Shale-shells	2215
Lime-shale	3380
K. C. Lime	3397
Lime	3636
Conglomerate	3668
Arbuckle Lime	3672'

RECEIVED  
STATE CORPORATION COMMISSION  
12-8-1969  
DEC 8 1969  
CONSERVATION DIVISION  
Wichita, Kansas

STATE

STATE OF KANSAS )  
                          ) ss  
RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

-----  
Subscribed and sworn to before me this 30th day of September, 1952.

-----  
Notary Public

My commission expires: 6-17-54.