


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County. Sec. 30 Twp. 10S Rge. 20 NE  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
C SE SW NW  
Lease Owner Petroleum, Inc.  
Lease Name Teall Well No. 3  
Office Address 800 R.H. Garvey Bldg., Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above  
Section Plot

Date Well completed 5-28 1981  
Application for plugging filed 5-28 1981  
Application for plugging approved 5-28 1981  
Plugging commenced 5-28 1981  
Plugging completed 5-28 1981

Reason for abandonment of well or producing formation  
no commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
-- 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3775  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	282	8-5/8	274	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 840', plug, 65 sx  
Fluid to 300', plug, 30 sx  
Fluid to 40', plug, 10 sx  
Rat hole 5 sx



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DNR DRILLING CO  
515 R.H. Garvey Bldg.  
Wichita Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
James L. Donelson, Jr. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson Jr  
515 R.H. Garvey Bldg., Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 81

My commission expires April 30, 1983

Dorothy L. Schmidt  
Dorothy L. Schmidt Notary Public.

DOROTHY L. SCHMIDT  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appt. Exp. April 30, 1983

DRILLER'S LOG

PETROLEUM, INC.  
 Teall No. 3  
 C SE SW NW  
 Sec. 30-10S-20W  
 Rocks Co., Ks.

Commenced: 5-21-81  
 Completed: 5-28-81

Surface Casing: 274' of 8-5/8"  
 cmtd w/175 sx common, 2% gel,  
 3% cc

FORMATIONDEPTH

Surface Hole	0 - 282
Shale	282 - 580
Shale & Sand	580 - 1585
Anhydrite	1585 - 1633
Shale & Lime	1633 - 2260
Lime & Shale	2260 - 2830
Shale & Lime	2830 - 3135
Lime & Shale	3135 - 3600
Lime	3600 - 3775 RTD

I do hereby that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson, Jr.*  
 James L. Donelson, Jr.

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 29th day of May, 1981.

*Dorothy L. Schmidt*  
 Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT  
 STATE NOTARY PUBLIC  
 Sedgwick County, Kansas  
 My Appt. Exp. April 30, 1983

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN - 4 - 1981

CONSERVATION DIVISION  
 Wichita, Kansas