

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-02209-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Allphin

WELL NUMBER #2

SPOT LOCATION C S/2 SW NE

SEC. 30 TWP. 10 RGE. 20 XXXX-1W

COUNTY Rooks

Date Well Completed 4-8-85

Plugging Commenced 4-10-85

Plugging Completed \_\_\_\_\_

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS Hwy. 50 West, P.O. Box 399, Garden City, KS 67846

PHONE # (316) 275-7461 OPERATORS LICENSE NO. 4058

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing-KC Depth to top 3439 bottom 3460 T.D. 3703  
Arbuckle 3657 3703

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	Oil	3439	3460	5 1/2		None
Arbuckle	Oil	3657	3703	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from 0 feet to 550 feet each set. Squeezed Dakota with tubing & packer - used 250 sx. 60/40 pos., 6% gel, 3% calcium chloride - Finished plugging well down casing - used 180 sx. 60/40 pos., 6% gel, 3% calcium chloride, 5 sx. hulls. Ran 1 wooden plug and a 40 ft. cement plug to surface. Pressured up on casing and surface pipe annulus and held 400 lbs.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B J TITAN License No. \_\_\_\_\_  
Address 1707 E. 10th, Hays, KS 67601

STATE OF KANSAS COUNTY OF ELLIS, ss.

Isaidore P. Kisner (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Isaidore P. Kisner  
(Address) 3000 Broadway Ave., Suite C  
P.O. Box 1084  
Hays, KS 67601-1084



SUBSCRIBED AND SWORN TO before me this 10th day of September, 1985

RECEIVED  
Rosalind A. King  
Notary Public

My Commission expires: May 28, 1989

STATE CORPORATION COMMISSION  
Rosalind A. King

SEP 18 1985  
9-18-1985

CONSERVATION DIVISION

Form CP-4  
Revised 01-84