


15-065-00966-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 7 Twp. 10 S Rge. 21W (~~21X~~) (W)  
Location as "NE/CNW/SW" or footage from lines C/ NW NW SW  
Lease Owner Graham-Michaelis Drilling Co.  
Lease Name Mc Elroy Well No. 1  
Office Address 211 N. Broadway, Wichita, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 12/31/56 19\_\_  
Application for plugging filed 12/31/56 19\_\_  
Application for plugging approved 12/31/56 19\_\_  
Plugging commenced 12/31/56 19\_\_  
Plugging completed 12/31/56 19\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kans.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3974 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	213*	8 5/8	213*	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole bottom plug @ 200\* w/ 1/4 sack hulls  
under plug and 15 sacks cement thru drill pipe -  
Filled hole to 40\* w/ mud - Top plug @ 40\* w/ 1/4 sack  
hulls under plug and 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Michaelis Drilling Co.  
Address 211 N. Broadway, Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. A. Michaelis, Jr. (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GRAHAM-MICHAELIS DRILLING CO.  
(Signature) W. A. Michaelis, Jr. Managing Partner  
211 N. Broadway, Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 1957

My commission expires 6/23/58

Flo Duncan  
Flo Duncan Notary Public.

PLUGGING  
FILE SEC 7 T. 10 R. 21W  
BOOK PAGE 130 L. 13

RECEIVED  
STATE CORPORATION COMMISSION

01-07-57  
CONSERVATION DIVISION  
Wichita, Kansas

No. ELROY #1

Well Record

Location: NW/ NW/ SW/ Section 7-108-21W Commenced: 12/19/56  
Graham County, Kansas Completed: 12/31/56  
(rotary)

Operator: Graham-Michaelis Drilling Co.  
211 N. Broadway  
Wichita, Kans.

Contractor: Graham-Michaelis Drilling Co.  
211 N. Broadway  
Wichita, Kansas

Casing Record: 8 5/8" @ 213' w/ 600 sacks reg. cement

ME LOG

Surface hole	213
Red bed	<del>213</del> 1790
Line & shale	3420
Line	3778
Line & shale	3839
Line cherty	3871
Chert	3909
Congl. cherty	3958
Line	3974, RTD

STATE OF KANSAS )  
 ) ss.  
COUNTY OF SEDGWICK )

The undersigned, GRAHAM-MICHAELIS DRILLING CO., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING CO.

By John L. James  
John L. James, Geologist

Subscribed and sworn to before me  
this 4th day of Jany., 1957.

Flo Duncan  
Flo Duncan, Notary Public

My commission expires: 6/23/58

RECORDS  
SEC. 7 T. 10 R. 21W  
PAGE 130 LINE 13

OFFICE OF THE COMMISSIONER OF GEOL. & MIN. IND.  
DIVISION OF OIL & GAS  
WICHITA, KANSAS