

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 South Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-03,368-00-01

RECEIVED

AUG 08 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

LEASE NAME MCINTIRE

WELL NUMBER #4 (NW NW SE)

2310 Ft. from S Section Line
2310 Ft. from E Section Line

LEASE OPERATOR John O. Farmer, Inc.

SEC. 10 TWP. 10S RGE. 21 XXXXXX (W)

ADDRESS P.O. Box 352, Russell, KS 67665

COUNTY Graham

PHONE# (785) 483-3144 OPERATORS LICENSE NO. 5135

Date Well Completed April, 1953

Plugging Commenced 7-21-03

Plugging Completed 12:10 P.M., 7-21-03

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by _____ (District #4) _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Not available

Producing Formation Lansing/KC Depth to Top 3482' Bottom 3786' T.D. 3794'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|------------|-------------|-------|----------|--------|--------|------------|
| Lansing/KC | oil & water | 3478' | 3676' OA | 8-5/8" | 165' | -0- |
| | | | | 5-1/2" | 3788' | -0- |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug @ 2000' w/160 sks. cement & 300# hulls; 2nd plug @ 1400' w/55 sks. cement & 100# hulls. Pulled to 1100' w/40 sks. cement. Circulated to surface. Pulled tubing - pumped 15 sks. cement down 5-1/2" casing. Pressured to 700#. Shut in @ 500#. Pumped 50 sks. cement & 100# hulls down backside. Shut in @ 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.


STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III XXXXXXXXXXXXXXXXXXXXXXXXXXXX (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of th above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 6th day of August, 20 03



Margaret A. Schulte
Notary Public
Margaret A. Schulte

ALLIED CEMENTING CO., INC. 14749

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

| | | | | | | | |
|--|-----------------|---|-------|---------------------------|----------------------|-----------------|----------------------------|
| DATE <u>7/2/03</u> | SEC. | TWP. | RANGE | CALLED OUT <u>5:00 AM</u> | ON LOCATION | JOB START | JOB FINISH <u>12:10 PM</u> |
| LEASE <u>McIntire</u> | WELL # <u>4</u> | LOCATION <u>Church of God 225 Winto</u> | | | COUNTY <u>Graben</u> | STATE <u>Kn</u> | |
| <input checked="" type="radio"/> OLD OR NEW (Circle one) | | | | | | | |

CONTRACTOR POF

TYPE OF JOB Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 3/8 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED _____

375 lbs 60/40 - 10

500 # Halls used 320 lbs

| | | | | |
|--------------|-------------|---|-------------------|----------------|
| COMMON | <u>192</u> | @ | <u>7.25</u> | <u>1372.00</u> |
| POZMIX | <u>128</u> | @ | <u>3.00</u> | <u>486.40</u> |
| GEL | <u>22</u> | @ | <u>10.00</u> | <u>220.00</u> |
| CHLORIDE | | @ | | |
| <u>Halls</u> | <u>5</u> | @ | <u>18.00</u> | <u>90.00</u> |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| HANDLING | <u>375</u> | @ | <u>1.15</u> | <u>431.25</u> |
| MILEAGE | <u>54.5</u> | @ | <u>15.00/mile</u> | <u>817.50</u> |
| TOTAL | | | | <u>3444.30</u> |

COPY

RECEIVED
AUG 08 2003
KCC WICHITA

EQUIPMENT

PUMP TRUCK CEMENTER Bill

366 HELPER Paul

BULK TRUCK

254 DRIVER Scott

BULK TRUCK

_____ DRIVER _____

REMARKS:

SERVICE

1st plug @ 2000' w/ 160 lbs of 300 # Halls

2nd plug @ 1400' w/ 55 lbs of 100 # Halls

pull to 1100' w/ 40 lbs Circ. to surface

pull tubing, pump down 55 w/ 1 side

press to 700' 500 shut in

500 lbs backside 100 # Halls

500 # Halls 500 ST

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE @ _____

MILEAGE 45 @ 3.50 157.50

PLUG @ _____

TOTAL 632.50

CHARGE TO: J.O. Farmer

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE James Coleman

PRINTED NAME _____