


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

GRAHAM County. Sec. 10 Twp. 10S Rge. (E) 21 (W)
Location as "NE/CNW*SW*" or footage from lines C E/2 SW NE
Lease Owner UNION TEXAS PETROLEUM
Lease Name BARTOS Well No. 8
Office Address 1740 BROADWAY, DENVER, COLORADO
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed _____ 19____
Application for plugging filed APRIL 28 19 66
Application for plugging approved _____ 19____
Plugging commenced MAY 2 19 66
Plugging completed MAY 9 19 66
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3826 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245	NONE
				5 1/2"	3826	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5-2-66 PUMPED 40 SACKS GEL MUD AND 50 SACKS CEMENT DOWN 5 1/2" CASING.
5-4-66 STATE SUPERVISOR CHECKED WELL AND FOUND FLUID AT 145' AND CEMENT AT 946'.
5-9-66 RAN 2" TUBING TO 600'. PUMPED 8 SACKS QUICK SET CEMENT, WAITED ONE HOUR, THEN PUMPED 65 SACKS CEMENT TO BASE OF CELLAR.

[Handwritten notes and stamps]
06-13-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

BOX 562, GREAT BEND, KANSAS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 10TH day of JUNE, 1966

My commission expires JULY 31, 1966

[Signature]
Notary Public.

DRILLER'S LOG

Company: Anderson-Frithard Oil Corp.

C - E/2 SW/4 NE/4
Sec. 10, Twp. 10N, Rge. 21W

Name: Curtis Well No. 8
Total Depth: 3826'

County: Graham,
Kansas

Date: 10-10-51 Comp: 10-20-51
Contractor: Glenn W. Feel
Casing:

Elevation:

8 5/8" 245' cen.
3 1/2" 3825' cen.

Production:

Figures below indicate bottom of formations

Surface Soil	0 -	245
Clay		850
Loam		1020
Shale & Shells		1250
Sand & Shale		1575
Shale		1770
Argillite		1800
Shale & Shells		2405
Shale & Lime		2930
Lime		2995
Lime & Shale		3145
Lime		3715
Lime & Shale		3812
Lime		3826
Total Depth		3826

RECEIVED
OIL CORPORATION COMMISSION
DEC 8 1951

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. FEEL

BY: Manan M. Herbert

SUBSCRIBED AND SWORE to before me this 23rd day of October, 1951.

My commission expires June 4, 1955 Manan M. Herbert
Notary Public

Elevation: 2277 RB

Heebner 3477 (-1200)
Lansing 3517 (-1240)
Congl. 3795 (-1518)
Simpson 3813 (-1534)
Arbuckle 3825 (-1548)
R.T.D. 3827 (-1550)

DST #1 3545-65. Op 1/2 hr. Rec. 220' salt water, Slightly gas cut. BHP 1150#.
DST #2 3790-3814. Op 30 min. Rec. 7' mud and little oil in tool. No BHP. Light blow for 7 min.
Drld cem. & CO to RTD 3827. Swbd 8 BO / 1 BWP/3 hrs. Swbd 4 1/2 BO / .4 of 1% wtr per hour/24 hours. Ran tubing and rods. POP

Initial Potential: 12,121 BO / no wtr in 24 hours. (Drawdown)