

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 10 Twp. 10 Rge. -- (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines E2 NW NE
Lease Owner Rocket-Schusterman Oil Account
Lease Name Bartos Well No. 4
Office Address 2700 First National Tower, Tulsa, OK 74103
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 4 19 51
Application for plugging filed December 16 19 82
Application for plugging approved December 23 19 82
Plugging commenced March 18 19 83
Plugging completed March 18 19 83
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production No record 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Carl Goodrow
Producing formation Arbuckle Depth to top 3822 Bottom 3829 Total Depth of Well 3829 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	3824	3829	5 1/2	3825	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from Surface feet to 3000 feet for each plug set.

Pumped 10 sacks of Poz mixed with 2 sacks of Hulls, followed by 18 sacks of Gel and 100 sacks of cement. All cement 50-50 Poz mix with 6% gel and 3% CaCl. Shut in casing at 11:30 A.M. Top of cement stopped at 300 feet from surface, then dumped 1 1/2 yards of Redi-Mix concrete and filled hole to surface. Well plugged and abandoned.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Samson Resources Company (Operator for R.S.O.A. Oper. License #5463)
Address 2700 First National Tower, Tulsa, OK 74103

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
R. J. Davis, Employee of Owner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Davis
2700 First National Tower, Tulsa, OK 74103
(Address)

Subscribed and Sworn to before me this 24th day of March, 1983

Blonda Kay Goodrow
Notary Public.

My commission expires Sept. 29, 1985

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1983

CONSERVATION DIVISION
Wichita, Kansas

BARTOS #4 WELL

LOCATION: Cen. E $\frac{1}{2}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$ SEC. 10-10S-21W
Graham County, Kansas

OPERATOR: Anderson-Prichard Oil Corporation

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 84.17' of 9-5/8" and 158.31' of 9"
casing cemented at 239' with 200 sacks cement and 2.c.c.

OIL STRING: 5 $\frac{1}{2}$ " 14# casing set at 3824' with
125 sacks cement.

SPUDED: 2-19-51

COMPLETED: 3-2-51

LOG

(Figures indicate bottom of formation)

0	to	248	Surface
		725	Shale
		780	Sand
		1310	Shale and sand
		1500	Sand
		1768	Shale and red bed
		1805	Anhydrite
		2155	Shale
		2325	Shale and shells
		2455	Lime and shale
		2580	Shale
		2865	Lime and shale
		3235	Shale
		3285	Lime and shale
		3330	Lime
		3390	Lime and shale
		3826	Lime
		3826	Total Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Bartos No. 4 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY

Richard Hindery

Subscribed and sworn before me
this 5th day of March, 1951.

Walter J. Ginger
Notary Public

My commission expires November 29, 1954.

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1951

CONSERVATION DIVISION
Wichita, Kansas