

15-065-02493-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME BARTOS

WELL NUMBER 2

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 10 TWP. 10S RGE. 21 (X) or (W)

COUNTY GRAHAM

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-5-91

Plugging Completed 12-6-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR BRITO OIL CO., INC.

ADDRESS 200 EAST FIRST, SUITE 208, WICHITA, KS 67202

PHONE#(316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-4-91 (date)

by CARL GOODROW (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? \_\_\_\_\_

Producing Formation ARBUCKLE Depth to Top 4034 Bottom 4338 T.D. 4338

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
ARBUCKLE	SALTWATER	246	0	10-3/4	246	NONE
		4034	0	5-1/2	4034	NONE
		3250	0	3-1/2	3250	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH W/ 1-3/4" DRILL PIPE. SPOTTED 20 SX CMT @ 3250'. SPOTTED 30 SX CMT @ 2950'. TOH W/ DRILL PIPE. PERF 3-1/2" TBG W/ 2 JS @ 1600' & 2 JS @ 1100'. PUMPED 50 SX CMT THEN 500# HULLS IN 250 SX CMT DOWN TBG. SDFN. RAN MEASURING LINE & TAGGED CMT @ 545'. PUMPED 25 SX DOWN TBG & CIRC CMT TO SURFACE. SI ANNULUS & STAGED TO 300#. SI HOLDING 200#. PLUGGED W/ 375 SX TOTAL 65-35 POZ W/ 10% GEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor CHASE WELL SERVICE License No. 6123

Address P.O. BOX 355, GREAT BEND, KS 67530-0355

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BRITO OIL CO., INC. 03-25-92

STATE OF KANSAS COUNTY OF BARTON, ss.


THOMAS C. LARSON AGENT ~~KXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas C. Larson

(Address) P.O. BOX 553, GREAT BEND, KS 67530-0553

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1992

Sherril J. Donnan  
Notary Public



My Commission Expires: September 28, 1993