

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
7-28-1967
JUL 28 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.,

Complete Address: R. R. # 2 Great Bend, Kansas 67530

Lease Name Teall Well No. 2

Location C W/2 SW NW Sec. 30 Twp. 10 Rge. 20 (E) (W) X

County Rooks Total Depth 3749

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Casing Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 3 P Day 26 Month 7 Year 1967

The Above well was plugged as follows:

Total Depth 3749' 8 5/8 csg set at 216' cwc 175 sc.

5 1/2 csg set at 3748' cw 100 sc cement.

PB 3744' and perf. (3728-40)

Filled with sand to 3700' and dumped 5 sc cement with dump bailer.

Recov. 3051' of 5 1/2 csg.

Pumped thru 8 5/8 plg. container with 26 sc gel (3950-820) 150 sc poz cement (820-160)

4 sc gel (160-35) and 10 sc cement 35 to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 7/28/67

INV. NO. 6030-u