

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 163-21,321 ✓

Operator's Full Name PETROLEUM, INC.

Complete Address 300 WEST DOUGLAS, R.H. GARVEY, BLDG. WICHITA, Mo.

Lease Name TEALL Well No. #3

Location 60'N-C-SE-SW-NW Sec. 30 Twp. 10^S Rge. 20^W (East) (West)

County ROOKS Total Depth 3775 FE.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor D. N. B. DRILLING

Address 515 RH. GARVEY, BLDG. WICHITA^{Mo.} License No. _____

Operation Completed: Hour: 6:30^{AM} Day: 28 Month: MAY Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" 282 FE SP. CMC^W/175^{SE} COMMON-2% GEL-3% CA-CL.

ORDERED 110^{SE} 50/50 Permox 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1^{SE} PLUG. @ 840 FE ^W/65^{SE} CNT.

2ND PLUG. @ 300 FE ^W/30^{SE} CNT.

3RD PLUG. - SOLID BRIDGE @ 40 FE ^W/10^{SE} CNT.
HULLS- PLUG.

5^{SE} IN RAT HOLE

CEMENTED BY SUN CNT.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

5-29-1981
MAY 29 1981

INVOICED

Signed: Marion Schmidt
Conservation Division Agent
Conservation Division
Wichita, Kansas

DATE 6-26-81

INV. NO. 5756-W