

15-065-01127-0000

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address: Box 169 Russell Kansas

Lease Name Germany Well No. 2

Location SE NE NE Sec. 6 Twp. 10 Rge. 21 (E) (W)

County Graham Total Depth 3890

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 3p Day 15 Month July Year 1968

The Above well was plugged as follows:

3890
T.D.- 8 5/8 set 4t-- 233 CWC 200 sax 5 1/2" set at 3885'

Sand to 3500' and 5 sax cement, dumped with dump bailer

Squeezed with 30 sax gel, 5 sax hulls, and 130 sax cement, in the following manner,

Squeezed 19 sax gel and 4 sax hulls and 100 sax cement, (cement from 850' to 525')

mud from 525 to 245' and 20 sax cement, (cement from 245' to 185'), mud from 185' to

30' and 1 sac hulls and 10 sax cement, (hulls and cement from 30' to base of cellar.

Squeezed by Allied Cementing Co. Russell Kansas

I hereby certify that the above well was plugged as herein stated, Gilbert P. Leiker

Signed: Gilbert P. Leiker
Well Plugging Supervisor

INVOICED

DATE 7/17/68

INV. NO. 8134-W