

15-065-01128-0001

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address: Box 169 Russell Kansas

Lease Name Germany Well No. 3

Location NW NE NE Sec. 6 Twp. 10 Rge. 21 (E) (W)

County Graham Total Depth 3906

Abandoned Oil Well Gas Well Input Well SWD Well D & A
RT KCC

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 5p Day 15 Month July Year 1968

The Above well was plugged as follows:

3906
~~T.D. 8 5/8 set at 239' 5 1/2" set at 3901 cwc 125 sac
Sand to 3500' and 5 sac cement, dumped with dump bailer
Squeezed with 30 sac gel, 5 sac hulls, and 130 sac cement, in the following manner,
Squeezed 19 sac gel and 4 sac hulls and 100 sac cement, (cement from 850' to 525')
mud from 525 to 245' and 20 sac cement, (cement from 245' to 185'), mud from 185' to
30' and 1 sac hulls and 10 sac cement, (hulls and cement from 30' to base of cellar.
Squeezed by Allied Cementing Co. Russell Kansas~~

I hereby certify that the above well was plugged as herein stated.

Signed: Gilbert P. Leiker
Well Plugging Supervisor

INVOICED
DATE 7/17/68
INV. NO. 8135-W