

15-065-20296-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Imperial Oil Company,
Complete Address Box #784, Great Bend, Kansas.
Lease Name Hansen Estate Well No. 1
Location NW-SW-SW Sec. 6 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3971'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated _____
Plugging Contractor Above
Address _____ License No. _____
Operation Completed: Hour 11:30 PM Day 1 Month 1 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 725'.
Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru
DP from 950' to 625'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

RECEIVED
JAN 5 1970
WV. NO. 1189-W