

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1970  
CONSERVATION DIVISION  
Wichita, Kansas

**J. Lewis Brock**  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name D. G. Hansen Estate,

Complete Address Box #187, Logan, Kansas.

Lease Name Brown Estate Well No. 2

Location SW-NE-NW Sec. 6 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3891'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 11:45 AM Day 18 Month 6 Year 1969

The above well was plugged as follows:

128'--8 5/8" Surface casing, cement circulated with 115 Sx.  
3890'--5 1/2" casing cemented on bottom with 150 Sx. Well plugged back to 3656'. Top perforations from 3581' to 3609'. Top of cement @ 650' (Temperature Survey). DV tool set @ 1769' with 550 Sx. cement.

Sanded well back to 3570' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 90 Sx. cement then 4 sacks gel and followed with 35 Sx. cement then 2 sacks gel and finally 10 Sx. cement. Maximum pump-in pressure--200#. Final shut-in pressure-150#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

**INVOICED**

DATE 6/22/70  
INV. NO. 2085-W