

15-065-01133-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D. G. Hansen Estate,

Complete Address Box #187, Logan, Kansas,

Lease Name Brown Estate Well No. 1

Location NE-NE-NW Sec. 6 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3867'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 18 Month 6 Year 1970

The above well was plugged as follows:

148'--8 5/8" Surface casing, cement circulated with 125 Sx.
3866'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
3600'. Top perforations from 3588' to 3590'. DV tool set @ 1749' with 500 Sx. cement.
Top of cement @ 800'--(Temperature Survey).

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with 90 Sx. cement then 8 sacks gel and followed with 35 Sx. cement
then 2 sacks gel and finally 10 Sx. cement. Maximum pump-in pressure-250#. Final
shut-in pressure-200#. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/22/70
INV. NO. 2084-W