

15-065-00841-0000

KANSAS

Form CP-3
Rev. 6-26-62

P
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
AUG 17 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name D. G. Hansen.

Complete Address: Logan, Kansas.

Lease Name McElroy Well No. 1

Location SE-SE-SE Sec. 7 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3842'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Incorporated.

Address: Box #364, Great Bend, Kansas. License No. 496

Operation Completed: Hour 7:00PM Day 14 Month 8 Year 1967

The Above well was plugged as follows:

175'--8 5/8" Surface pipe, cement circulated.
3833'--5 1/2" Production casing cemented with 175 Sx. Well plugged back to
3760'. Top perforation @ 3756'. Dakota section from 1150' to 1375'.

Pushed plug to 3600', built 10' rock bridge and set 5 Sx. cement with DB.

Pulled 5 1/2" casing to 1375' and circulated heavy gel mud with 25 Sx. gel.

Pulled 5 1/2" to 1325' and displaced 100 Sx. cement thru 5 1/2". Pulled 5 1/2" to

180' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @

35' and 5 Sx. cement to bottom of cellar. (Recovered 2724' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/17/67

INV. NO. 6157-

Signed: W. L. Nichols
Well Plugging Supervisor