

15-065-20552-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name McElroy Well No. 2

Location N/2-SW-SE Sec. 7 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 9:30 AM Day 16 Month 6 Year 1972

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Fitch*
Well Plugging Supervisor

INVOICED

DATE 6-29-72

INV. NO. 5926-W