

15-065-01706-0000

Form CP-3.
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply Inc.

Complete Address: Box 169 Russell Kansas

Lease Name Germany Well No. 1

Location NW SE NE Sec. 6 Twp. 10 Rge. 21 (E) (W)

County Graham Total Depth 3882

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 1 p Day 15 Month July Year 1968

The Above well was plugged as follows:

3882
T.D.- 8 5/8 set 4t--209 cwc

Sand to 3500' and 5 sax cement, dumped with dump bailer

Squeezed with 30 sax gel, 5 sax hulls, and 130 sax cement, in the following manner,

Squeezed 19 sax gel and 4 sax hulls and 100 sax cement, (cement from 850' to 525')

mud from 525 to 245' and 20 sax cement, (cement from 245' to 185'), mud from 185' to

30' and 1 sac hulls and 10 sax cement, (hulls and cement from 30' to base of cellar.

Squeezed by Allied Cementing Co. Russell Kansas

I hereby certify that the above well was plugged as herein stated. Gilbert P. Leiker

Signed: Gilbert P. Leiker
Well Plugging Supervisor

INVOICED

DATE 7/17/68

INV. NO. 8133-W