

15-065-19204-0001

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
NOV 14 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Okmar Oil Company.Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.Lease Name Bartos Well No. 1Location NW-NW-NW Sec. 10 Twp. 10 Rge. (E) 1021County Graham Total Depth 4284Abandoned Oil Well Gas Well Input Well SWD Well X D & A Other well as hereafter indicated: Plugging Contractor: Sun Oil Well Cementing, Inc.,Address: Box # 69, Hays, Kansas. License No. Operation Completed: Hour 11:30 AM Day 8 Month 11 Year 1966

The Above well was plugged as follows:

275'--8 5/8" Surface pipe, cement circulated.
3830'--5 1/2" casing, cement circulated. 4 1/2" liner from 3782' to 3942'
cemented in. 4 1/2" liner from surface to 1974' cemented in.

Squeezed well with 25 sacks gel and 2 sacks hulls followed by 75 sacks
cement with 3% Sun-Set. Did not encounter any pump-in pressure.

Checked well after 3 hours and found mud and cement had gone down hole
below 500'. Waited six days and filled hole from 750' to bottom of
cellar using 2 1/2 yards Redi-Mix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. T. J. J. J.

Well Plugging Supervisor

DATE

11/15/66

INV. NO.

4266-4