

15-065-01717-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum,

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name Bartos Well No. 8

Location CE/2-SW-NE Sec. 10 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3826

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 4:00PM Day 9 Month 5 Year 1966

The Above well was plugged as follows:

245'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3826'--5 1/2" Production casing. Well plugged back to 3721'. Top perfora-
tions @ 3710'. 5 1/2" squeezed in the Dakota Sands, no effort made to sal-
vage 5 1/2".

Squeezed well with 40 Sx. gel followed with 50 Sx. cement. Pump-in press-
ure 500#. Final shut-in pressure 300#. Check well after cement had a
chance to set and found fluid @ 145' and cement @ 946'. Ran 2" tubing to
600' and displaced 8 Sx. "Quick-Set" cement thru tubing. Waited 1 hour
for plug to set and checked with 2" tubing then circulated cement thru
2" to top of hole using 65 Sx. cement.

(Final cementing operations performed by Globe Oil Well Cementing.)

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/11/66
INV. NO. 3199-U