

15-065-01712-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED

APR 27 1967  
04-27-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum,

Complete Address: Suite B-400, 1740 Broadway, Denver, Colorado.

Lease Name Bartos Well No. 3

Location NW-NW-NE Sec. 10 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3842

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Santa Fe Pipe & Supply, Incorporated,

Address: Box # 562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 2:00PM Day 24 Month 4 Year 1967

The Above well was plugged as follows:

259'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
3842'--5 1/2" Production casing cemented with 125 Sx. Well plugged back to 3800'. Top perforations @ 3652'.

Pushed plug to 3600' and sanded back to 3575'. Dumped 5 Sx. cement on topsand bridge with dump bailer. Pulled 5 1/2" casing. Squeezed well with 50 Sx. gel using 6 Sx. hulls in initial gel and followed with 75 Sx. cement. Maximum pump-in pressure 300#. Final shut-in pressure 150#.

(Mudding and cementing operations performed by Globe Cementing)

(Recovered 812' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/27/67

INV. NO. 5728-W

Signed: W. L. Dickel  
Well Plugging Supervisor