

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling, Inc. has this

date requested permission to plug the following described well:

Union Texas Petroleum, Inc.,

Mr. Pully guarantees payment of the plugging fee.Operator's full Name: Union Texas Petroleum, Incorporated,Complete Address: Drawer "D", Great Bend, Kansas.Lease Name: C. L. Miller Well No. 4Location: NE-SE-SW Sec. 3 Twp. 10 Rge. (E) (W) 21County Graham Total Depth 3852 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Pully was instructed to plug the well as follows:265'--8 5/8" Surface pipe, cement circulated.3851.5'--5 1/2" Production casing cemented with 125 Sx. 5 1/2" squeezed @ 500'.

Sand well back to 3820' and set 4 Sx. cement with dump bailer.
Set plug at base of surface and displace 20 Sx. cement thru 5 1/2".
Heavy gel mud to 40', set 10' rock bridge and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. D. Nichols