

15-023-02581-00001

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Perkins of Rocket-Schusterman has this
date requested permission to plug the following described well:

Mr. Perking guarantees payment of the plugging fee.

Operator's full Name: Rocket-Schusterman Oil Account,

Complete Address: 1209 Mid-Continent Building, Tulsa, Oklahoma.

Lease Name: Miller Well No. 7

Location: SW-NW-SW Sec. 3 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 4300' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Perkins was instructed to plug the well as follows:

237'--8 5/8" Surface casing, cement circulated.

3998'--5 1/2" casing cemented on bottom with 450 Sx with 2-stage collar @
1804' and 150 Cu. Ft. "Stratocrete". (Open hole completion).

Squeeze well with 5 sacks hulls, 40 sacks gel and 85 Sx. cement, staged.
Attempt to pump down annulus.

Very truly yours,

Conservation Division Agent