



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Chambers of Okmar Oil Company has this date requested permission to plug the following described well:

Mr. Chambers guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Kern Well No. 3

Location: SE-NW-SE Sec. 4 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3876' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Chambers was instructed to plug the well as follows:

103'--8 5/8" Surface casing, cement circulated with 60 Sx.
3874'--5 1/2" casing cemented on bottom with 125 Sx. 5 1/2" has been squeezed
@ 1385' with 150 Sx. and @ 1480' with 150 Sx. cement. 4 1/2" liner set @
1759' with cement circulated to surface.

Squeeze well with 30 sacks gel and 75 sacks cement, staged. Try to pump
down annulus with clear water if it is open squeeze with 10 Sx. gel and
50 Sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent