



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Chambers of Okmar Oil Company, has this  
date requested permission to plug the following described well:

Mr. Chambers guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers-KSB&T Bldg., Wichita, Kansas.

Lease Name: Kern Well No. 5

Location: W/2-SE-SE Sec. 4 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3873' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Chambers was instructed to plug the well as follows:

118'--8 5/8" Surface casing, cement circulated.  
3870'--5 1/2" Production casing cemented on bottom with 100 Sx. Bottom of  
5 1/2" sanded back to 3840' with Frac Sand. 5 1/2" has been squeezed thru  
leak, no attempt to recover 5 1/2" casing.

Run measuring line on 5 1/2" casing to determine fluid level and establish  
whether or not 5 1/2" has broken in. If so, squeeze 5 1/2" with 5 sacks hulls,  
30 sacks gel and 135 Sx. cement. Attempt to pump cement down 8 5/8-  
5 1/2" annulus.

Very truly yours,

*M. L. Nichols*  
Conservation Division Agent