

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Larry Horner of Southwest Csg Pulling Co. has this

date requested permission to plug the following described well:

Okmar Oil Company

Mr. Horner guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 820 Union National Building, Wichita, Kansas.

Lease Name: Abiram Well No. A-1

Location: SE-SE-^{SW}SE Sec. 4 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3857 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Horner was instructed to plug the well as follows:

204'--8 5/8" Surface Pipe, cement circulated.
5 1/2" set @ 3852' cemented with 150Sx. Perforations from 3600
to 3616. Well squeezed @ 1180'.

Sand well back to 3590' and set 5 Sx cement with dump bailer.
Pull 5 1/2" to 600', circulate heavy gel mud and displace 20 Sx
cement thru casing. Pull 5 1/2" to 190 and displace 20 Sx cement
thru casing. Pull 5 1/2", set bridge @ 35' and 10 Sx cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent