



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Shively of Imperial Oil Company, has this

date requested permission to plug the following described well:

Mr. Shiveley guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: Box #784, Great Bend, Kansas.

Lease Name: Hansen Estate Well No. 1

Location: NW-SW-SW Sec. 6 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3971' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shiveley was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 950' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

K. L. Nichols  
Conservation Division Agent