

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:Mr. Unruh guarantees payment of the plugging fee.Operator's full Name: D. G. Hansen Estate.Complete Address: Box #187, Logan, Kansas.Lease Name: Brown Estate Well No. 2Location: SW-NE-NW Sec. 6 Twp. 10 Rge. (E)(W) 21County: Graham Total Depth 3891' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Unruh was instructed to plug the well as follows:

128'--8 5/8" Surface casing, cement circulated with 115 Sx.
3890'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged
back to 3656'. Top perforations from 3581' to 3609'. Top of cement @
650' (Temp. Survey). DV tool set @ 1769' with 550 Sx. cement.

Sand well back to 3570' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 6 sacks gel and 135 Sx.
cement, ~~removed~~ staged.

Very truly yours,

Conservation Division Agent