

15-065-02667-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. ~~122~~ 125-18  
LOCATION NE NW NE  
SEC. 6 TWP. 10 RGE. 21

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 5 Lease Beecher

Operator Great Bend Pipe & Supply Address Great Bend, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3897 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 147' circulated with cement - 5 1/2" at 3883' with 75 sax cement behind.

Filled with sand to 3870', set 4 sax cement with dump bailer, pulled 3000' 5 1/2" - filled with mud to 147', set rock and 16 sax cement, mud to 35', set rock and 10 sax cement to bottom cellar.

E. J. Perry  
District Conservation Agent

Date 6-10-55

**PLUGGING**  
FILE SEC 6 T 10 R 24W  
BOOK PAGE 125 LINE 18

06-22-55