

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Joe Espinosa of Southwest Csg. Pulling Co has this
date requested permission to plug the following described well:
D. G. Hansen
Mr. Espinosa guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen

Complete Address: Logan, Kansas.

Lease Name: McElroy Well No. 1

Location: SE-SE-SE Sec. 7 Twp. 10 Rge. (E)(W) 21

County Graham Total Depth 3842' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Espinosa was instructed to plug the well as follows:

175'--8 5/8" Surface pipe, cement circulated. 3833'--5 1/2"
Production casing cemented with 175 Sx. Well plugged back to
3760'. Top perforation @ 3756'. Dakota section from 1150' to
1300'.

Push plug to 3600', build rock bridge and set 5 Sx. cement with
dump bailer. Pull 5 1/2" to 1375' and circulate heavy gel mud.
Pull 5 1/2" to 1325' and displace 100 Sx. cement thru 5 1/2". Pull
5 1/2" to 180' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set
bridge @ 35' and 5 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent