

15-065-00312-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 12 TWP. 10 RGE. 21 E/W  
Location as in quarters or footage from lines:  
NW NW SW



Locate Well  
correctly on above  
Section Platt.

Lease Owner Galloway Drilling Co., Inc.  
Lease Name Bass Well No. 1  
Office Address 105 So. Broadway, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): oil  
Date Well Completed 6/4/50  
Application for plugging filed 5/20/83  
Plugging commenced 4/26/83  
Plugging completed 4/26/83  
Reason for abandonment of well or producing formation  
Lack of commercial production

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Arbuckle Depth to top \_\_\_\_\_ bottom T.D. 3831

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	228.40	none
				5 1/2	3828.49	none

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

160 sx 50-50 Poz 6% Gel + 3% CC  
31 sx Gel + 2sx hulls + 1 1/2" plug  
Plugged 3:30 p.m. 4/26/83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jay H. Galloway (~~employee of owner~~) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) J. H. Galloway  
**GALLOWAY DRILLING CO., INC.**  
344 Broadway Plaza Building  
105 South Broadway  
WICHITA, KANSAS 67202

SUBSCRIBED AND SWORN TO before me this 20th day of May

**EARLENE M. LUMRY**  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY APPT. EXPIRES: Sept. 7, 1985

Earlene M. Lumry  
Earlene M. Lumry Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1983

CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

Operator C-G Drilling Co. Inc. Farm Name Bass #1  
 Location NW/4 NW/4 SW/4 Sec. 12-10-21W.  
 Pool Name WC County Graham State Kansas  
 Commencement Date May 22, 1950 Completion Date June 1, 1950

LOG OF WELL

Elevation 2272' R.B.  
 All measurements from the top of rotary bushing.

DEPTH FROM	DEPTH TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	230			
230	735	Shale-Shells		
735	805	Sand		
805	915	Shale-Sand-Shells		
915	1105	Shale-Shells		
1105	1225	Sand		
1225	1450	Sand		
1450	1655	Sand-Shale		
1655	1748	Shale-Shells		
1748	1787	Anhydrite	1750' - 0°	
1787	1955	Shale-Shells		
1955	2215	Shale-Shells	2250' - 0°	
2215	2305	Shale-Shells		
2305	2400	Shale-Lime		
2400	2510	Shale-Lime		
2510	2620	Shale-Lime		
2620	2720	Lime-Shale		
2720	2860	Shale-Lime	2750' - 0°	
2860	2940	Shale-Lime		
2940	3000	Lime-Shale		
3000	3095	Lime-Shale	3000' - 0°	
3095	3230	Lime-Shale		
3230	3325	Lime-Shale		
3325	3395	Lime		
3395	3445	Lime		
3445	3515	Lime		
3515	3570	Lime		
3570	3630	Lime		
3630	3670	Lime		
3670	3735	Lime		
3735	3795	Lime		
3795	3831	Lime		

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 26 1983

CONSERVATION DIVISION  
 Wichita, Kansas

<sup>238.38'</sup> 8 CASING LEFT IN HOLE AFTER COMPLETION  
 Ran 228.40' (7 jts.) 8-5/8" OD Casing.  
 Set ~~228.40'~~ (120 jts.) 5-1/2" OD Casing.  
<sup>277.73'</sup> 97  
 STATE OF KANSAS, COUNTY OF SEDGWICK ) ss.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO. Inc.

By [Signature]  
 President

Subscribed and sworn to before me this 3rd day of June, 1950.

My commission expires:  
 June 25, 1951

[Signature]  
 Notary Public