

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 12 Twp. 10 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease Owner C-G Drilling Co.

Lease Name Hunt-Behrens Well No. 5

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil well

Date well completed January 18, 1956 19

Application for plugging filed August 22, 1962 19

Application for plugging approved August 23, 1962 19


Plugging commenced September 6, 1962 19

Plugging completed September 6, 1962 19

Reason for abandonment of well or producing formation no longer commercial

If a producing well is abandoned, date of last production 8/18/61 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3813 Bottom 3824 Total Depth of Well 3824 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	181.25	none
				5-1/2"	3814.00	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 2940'. Set plug. Filled with cement to top of hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 05 1962

09-25-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oilwell cementing, Inc.

Address P. O. Box 628, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jay H. Galloway (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of September, 1962

My commission expires May 20, 1963

Vicky Jacobs
Vicky Jacobs Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


15-0303J-0000

Company- C - G DRILG. CO.
 Farm- Hunt-Behrens No. 5

SEC. 12 T. 10 R. 21W
 NE SE SE

Total Depth. 3824'
 Comm. 1-9-56 Comp. 1-18-56
 Shot or Treated.
 Contractor.
 Issued. 6-9-56

County Rooks KANSAS



Elevation. 2213' RR.

Production. 66 BOPD

CASING:

8 5/8" 181.25' cem w/165 sx
 5 1/2" 3823.85' cem w/125 sx

Figures indicate Bottom of Formations.

surface	181
shale	500
shale	850
sand	950
shale	1250
sand	1495
red bed	1525
red bed & shale	1753
anhydrite	1790
shale, shells	2000
lime, shale	2290
lime, shale	3815
Arb. lime	3824
Total Depth	

Tops:	
Anhydrite	1753
Topeka	3371
Heebner	3476
Toronto	3501
Lansing	3518
Base Kansas City	3741
Conglomerate	3784
Arbuckle	3813

DST #1 3814-24, open 1 hr., strong blow throughout test. Red. 40' gas, 740' free oil, 80' muddy oil, BHP 500#.

RECEIVED
 STATE DEPARTMENT
 GEOLOGICAL DIVISION
 WASHINGTON, D.C.