


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 12 Twp. 10 Rge. 21 (E) W (W)
Location as "NE/CNWSW" or footage from lines NW NW NW
Lease Owner D. G. Hansen
Lease Name Sutor-Shields Well No. 5
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-13 1954
Application for plugging filed 7-13 1954
Application for plugging approved 7-13 1954
Plugging commenced 7-13 1954
Plugging completed 7-13 1954
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production -- 19--
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3887 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	162.28	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 40'; set plug;
1/2 sack hulls, 15 sacks cement. Filled
hole with mud to 40'; set plug then filled
to top with 10 sacks cement, 1/2 sack hulls.

CONSERVATION DIVISION
Wichita, Kansas
JUL 15 1954
07-15-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Building, Kansas, Wichita

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Vicky Jacobs (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vicky Jacobs Office Manager
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of July, 1954

Barbara Donaldson
Notary Public.

My commission expires June 17, 1957

PLUGGING
FILE SEC 12 T 10 R 21 W
BOOK PAGE 48 LINE 38

15-065-02369-0000

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Sutor-Shields #5
LOCATION NW NW NW, SECTION 12-10-21W,
POOL NAME Bass COUNTY Graham STATE Kansas
COMMENCEMENT DATE July 5, 1954 COMPLETION DATE July 13, 1954

LOG OF WELL

Elevation: 2288 R.B.
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	162	Shale		
162	450	Shale		
450	725	Sand-Shale		
725	815	Sand		
815	1260	Shale		
1260	1495	Sand		
1495	1555	Red Bed	0° - 1500'	
1555	1767	Red Bed		
1767	1805	Anhydrite		
1805	2075	Shale-Shells	0° - 2000'	
2075	2390	Lime-Shale		
2390	2575	Lime-Shale	0° - 2500'	
2575	2700	Lime-Shale		
2700	2905	Lime-Shale		
2905	2965	Shale-Lime		
2965	3095	Lime-Shale	0° - 3000'	
3095	3220	Lime-Shale		
3220	3330	Lime-Shale		
3330	3406	Lime-Shale		
3406	3475	Lime-Shale		
3475	3550	Lime-Shale	0° - 3500'	
3550	3604	Lime-Shale		
3604	3642	Lime-Shale		
3642	3680	Lime-Shale		DST 3632-42
3680	3740	Lime-Shale		
3740	3792	Lime-Shale		
3792	3865	Lime-Shale		
3865	3887	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 162'28 (5 js) 8-5/8" Surface Casing

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs
Office Manager

Subscribed and sworn to before me this 14th day of July, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
Notary public

PLUGGING
FILE SEC 12 T 10 R 2/W
BOOK PAGE 48 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1954
CONSERVATION DIVISION
Wichita, Kansas