

15-065-02456-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM

County. Sec. 12 Twp. 10S Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines N/2 N/2 NE/4

Lease Owner C-G DRILLING CO. & DLG. HANSEN

Lease Name HUNT-BEHRENS Well No. 7

Office Address 107 RULE BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed May 8 1956

Application for plugging filed May 8 1956

Application for plugging approved May 8 1956

Plugging commenced May 9 1956

Plugging completed May 9 1956

Reason for abandonment of well or producing formation TOO LOW STRUCTUALLY

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, HAYS, KANSAS

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 184' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 179'. Set plug. Put in 1/2 sack Hulls and 15 sacks of cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 56
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO. 05-12-56
Address 107 RULE BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 1956

Vicky Jacobs
Notary Public.

My commission expires May 20, 1959

PLUGGING
FILE SEC 12 T 10 R 21 W
BOOK PAGE 60 LINE 21

15-065-02456-0000

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. & D. G. HANSEN WELL NAME HUNT-BEHRENS #7

LOCATION N/2 N/2 SE/4 Sec. 12-10S-21W RIG NO. 1

COUNTY GRAHAM STATE KANSAS

COMMENCEMENT DATE APRIL 30, 1956 COMPLETION DATE MAY 9, 1956

LOG OF WELL

Elevation 2252' rotary bushing.
All measurements taken from top of rotary bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS |
|------|------|--------------|-------------------------|---------|
| 0 | 184 | Surface Soil | | |
| 184 | 780 | Shale | | |
| 780 | 1240 | Shale-Sand | | |
| 1240 | 1475 | Sand | | |
| 1475 | 1670 | Red Bed | | |
| 1670 | 1747 | Red Bed | | |
| 1747 | 2105 | Shale-Shells | | |
| 2105 | 2300 | Lime-Shale | | |
| 2300 | 2470 | Lime-Shale | | |
| 2470 | 2595 | Lime-Shale | 0° - 2500 | |
| 2595 | 2695 | Lime-Shale | | |
| 2695 | 2820 | Lime-Shale | 0° - 2750 | |
| 2820 | 2950 | Lime-Shale | | |
| 2950 | 3050 | Lime-Shale | 0° - 3000 | |
| 3050 | 3225 | Lime-Shale | | |
| 3225 | 3345 | Lime-Shale | 0° - 3250 | |
| 3345 | 3412 | Lime-Shale | | |
| 3412 | 3545 | Lime-Shale | 0° - 3500 | |
| 3545 | 3648 | Lime-Shale | | |
| 3648 | 3732 | Lime-Shale | | |
| 3742 | 3870 | Lime-Shale | 0° - 3720 | |
| 3870 | 3885 | Lime | | |
| 3885 | TD | | | |

CASING LEFT IN HOLE AFTER COMPLETION

184' of 8-5/8" OD Surface Casing

STATE OF KANSAS, COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

Subscribed and sworn to before me this 11th day of May, 1956.

My commission expires:
May 20, 1959

Vicky Jacobs
Vicky Jacobs, Notary Public

PLUGGING
WELL SEC. 12-10-21W
BOX MAIL 60 LINE 21