


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County. Sec. 12 Twp. 10 Rge. 21 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW NW NW
Lease Owner D. G. Hansen
Lease Name Sutor-Shields Well No. 6
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-15 1954
Application for plugging filed 10-15 1954
Application for plugging approved 10-15 1954
Plugging commenced 10-15 1954
Plugging completed 10-15 1954
Reason for abandonment of well or producing formation Too low structurally



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production -- 19---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	169.34	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 165'; set plug; 1/2 sack hulls, 15 sacks cement. Filled hole w/ mud to 40'; set plug then filled to top with 10 sacks cement, 1/2 sack hulls.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Vicky Jacobs (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____ Office Manager
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of October, 19 54

My commission expires June 17, 1957 _____ Notary Public.



10-19-54

15-065-02458-0000

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Sutor-Shields #6
 LOCATION SW NW NW, Sec. 12-10-21W
 POOL NAME _____ COUNTY Graham STATE Kansas
 COMMENCEMENT DATE 10-7-54 COMPLETION DATE 10-15-54

LOG OF WELL

Elevation: 2285 R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	170	Shale		
170	1250	Shale		
1250	1285	Sand		
1285	1445	Sand		
1445	1756	Red Bed	0° - 1500'	
1756	1797	Anhydrite		
1797	1975	Shale		
1975	2300	Shale-Lime		
2300	2465	Shale-Lime		
2465	2620	Lime-Shale	0° - 2500'	
2620	2830	Lime-Shale		
2830	2980	Lime-Shale		
2980	3035	Lime-Shale	0° - 3000'	
3035	3175	Lime-Shale		
3175	3315	Lime-Shale		
3315	3400	Lime-Shale		
3400	3490	Lime-Shale		
3490	3555	Lime-Shale	0° - 3500'	
3555	3610	Lime-Shale		
3610	3675	Lime-Shale		
3675	3735	Lime-Shale		
3735	3807	Lime-Shale		
3807	3870	Lime-Shale		
3870	3923	Chert-Shale		
3923	3950	Chert-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 169.34 (6 jts) of 8-5/8" Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By _____
 Office Manager

Subscribed and sworn to before me this 18th day of October, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
 Notary Public

