


15-065-02457-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 12 Twp. 10 Rge. 21 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NE NE
Lease Owner D. G. Hansen
Lease Name Bass "B" Well No. 2
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 17 19 57
Application for plugging filed February 17 19 57
Application for plugging approved February 17 19 57
Plugging commenced February 17 19 57
Plugging completed February 17 19 57
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2818 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 171' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 166'. Set plug. Put in 1/2 sack of Hulls & 15 sacks of cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack of Hulls & 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF SEDGWICK, ss.
Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
Jay H. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of February, 19 57

Vicky Jacobs
Vicky Jacobs
Notary Public.

My commission expires May 20, 1959

PLUGGING
FILE SEC. 12 T 10 R 21 W
BOOK PAGE 142 LINE 6

RECEIVED
02-20-57

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen WELL NAME Bass "B" #2
 LOCATION SE NE NE Sec. 12-10-21W RIG NO. 1
 COUNTY Graham STATE KANSAS
 COMMENCEMENT DATE February 6, 1957 COMPLETION DATE February 17, 1957

LOG OF WELL

Elevation 2262' rotary bushing.
 All measurements taken from the top of rotary bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS: |
|------|------|--------------|-------------------------|----------|
| 0 | 171 | Surface Soil | | |
| 171 | 875 | Shale-Sand | | |
| 875 | 1675 | Sand-Shale | | |
| 1675 | 1740 | Red Bed | | |
| 1740 | 1780 | Anhydrite | | |
| 1780 | 2075 | Shale-Shells | | |
| 2075 | 2325 | Shale-Lime | | |
| 2325 | 2450 | Shale-Lime | | |
| 2450 | 2685 | Lime-Shale | 0° - 2500 | |
| 2685 | 2770 | Lime-Shale | 0° - 2750 | |
| 2770 | 2940 | Lime-Shale | | |
| 2940 | 3055 | Lime-Shale | 0° - 3000 | |
| 3055 | 3250 | Lime-Shale | 0° - 3250 | |
| 3250 | 3355 | Lime-Shale | | |
| 3355 | 3505 | Lime-Shale | 0° - 3500 | |
| 3505 | 3570 | Lime | | |
| 3570 | 3688 | Lime-Shale | | |
| 3688 | 3855 | Lime-Shale | 6° - 3750 | |
| 3855 | 3910 | Lime-Shale | | |

CASING LEFT IN HOLE AFTER COMPLETION

Ran 171' (8 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
 By Jay H. Galloway
 Jay H. Galloway

Subscribed and sworn to before me this 19th day of February, 1957.

Vicky Jacobs
 Vicky Jacobs, Notary Public

My commission expires: May 20, 1959

PLUGGING
 SEC. 12 10 21W
 142 6

RECORDED