

15-065-01737-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 8-16-50

LEASE NAME BASS

WELL NUMBER #2

1650 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 12 TWP. 10 SRGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 8-16-50

Plugging Commenced 1-16-95

Plugging Completed 1-16-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Galloway Drilling Co., Inc.

ADDRESS 105 S Broadway Suite 340

PHONE# (316) 263-1793 OPERATORS LICENSE NO. 5783

Character of Well Oil - T.A.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-12-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? No Log ran

Producing Formation Arbuckle Depth to Top 3814 Bottom T.O. 3824

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf	267	8 5/8"		None
		Surf	3814	5 1/2"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran tubing to 2240' spotted 50 sx & 100# hulls, pulled to 1360' spotted 50 sx 150# hulls, pulled up 450', circulated cement to surface. 40 sx 50# hulls, pulled tubing. Hooked to 5 1/2" Squeezed 60 sx 100# hulls, max 250#, shut in 100# Hooked to 8 5/8", 50 sx 100# hulls 250# max press., shut in 100#
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Galloway Drilling Co. Inc. License No. 5783

Address 105 S Broadway Suite 340

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Same

STATE OF Kansas COUNTY OF Sedgwick, ss. MAR 27 1995

Jay H. Galloway

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

PATTI E. CARUTHERS
Notary Public - State of Kansas
My Appt. Expires 5-17-97

(Signature) [Signature]

(Address) _____

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 95

Patti E. Caruthers
Notary Public

My Commission Expires: 5-17-97